

#### **GENERAL NOTE:**

- 1. FOR ADDITIONAL INFORMATION, SEE CONTRACT DOCUMENT SHEET A108 AND ADDITIONAL PLANS AND SPECIFICATIONS AS APPLICABLE.
- 2. VENEER TO BE APPLIED IS NOT INCLUDED WITH THIS WORK AND SHALL BE PROVIDED AS REFERENCED ON CONTRACT DOCUMENT A108 AND ADDITIONAL PLANS AND SPECIFICATIONS AS APPLICABLE.

## **DEVELOPED ELEVATION**

SCALE: 1" = 20'



SCALE

NOTED

THIS DRAWING IS FURNISHED SOLELY FOR REV.NO.

THIS DRAWING IS FURNISHED SOLELY FOR REV.NO.

THE USE OF OR IN CONNECTION WITH THIS PROJECT AND THE PROPRIETARY INTRIBUTED TO ANY THE PROPRIETARY INTERPRETARY INTRIBUTED TO ANY THE PROPRIETARY INTRI DATE BY | DESCRIPTION 10/21/19 KH LAYOUT BASED ON CONTRACT PLANS 1/21/20 KH MAT REINFORCING & FASCIA KH BOT. OF WALL LOWERED FOR 2' MIN. COVER 2/6/20

GRAPHIC SCALE LINE IS 20 UNITS LONG ON ORIGINAL DRAWING

ENGINEER KBH CADD BY

PROJ. MGR.


KBH

1902 Hilfiker Lane Eureka, CA 95503-571 TOLL-FREE 800.762.8962 PH 707.443.5093 FAX 707.443.2891 WEB SITE www.hilfiker.com E-MAIL Info@hilfiker.com




ENGINEERED FOR CONSTRUCTION ARTWELD GABION (EXCLUDE VANEER) HARRISON SPECIALTY CARE CLINIC 1950 NW MYHRE RD., SILVERDALE, WA 98383 DEVELOPED ELEVATION

PROJECT 190801HG SHEET of 2




## STEP I

- 1. PLACE SOIL REINFORCEMENT MATS ON PREPARED FOUNDATION.
- 2. PLACE THE FIRST LIFT OF GABIONS AND PERMANENTLY CONNECT THE FRONT EDGES TO THE SOIL REINFORCEMENT MATS WITH SPIRAL BINDERS.
- 3. INSTALL FILTER FABRIC, IF REQUIRED.
- 4. PLACE AND COMPACT THE FIRST COURSE OF BACKFILL ON THE SOIL REINFORCEMENT MATS. BACKFILL TO BE OF SUFFICIENT DEPTH TO PROTECT SOIL REINFORCEMENT MATS FROM DAMAGE OR MOVEMENT BY EQUIPMENT DURING DELIVERY OF ROCK TO THE GABIONS.
- 5. FILL THE GABIONS WITH SUITABLE ROCK.
- 6. CLOSE LID AND SECURE WITH SPIRAL BINDERS.



#### STEP 2

- 1. PLACE AND COMPACT THE REMAINING BACKFILL IN UNIFORM LIFTS OVER THE SOIL REINFORCING MAT.
- 2. PLACE SOIL REINFORCEMENT MATS ON THE BACKFILL AND THE TOP OF THE GABION.
- 3. PLACE THE SECOND LIFT OF GABIONS OVER THE FIRST LIFT AND CONNECT THE GABIONS AND THE SOIL REINFORCEMENT MATS TOGETHER PERMANENTLY WITH SPIRAL BINDERS.
- 4. PLACE AND COMPACT BACKFILL AT THE TOE OF THE WALL PER YOUR PROJECT PLANS.



### STEP 3

1. REPEAT STEP 2 TO THE TOP LIFT OF GABIONS.

NOT TO SCALE

2. PLACE THE FINAL LIFT OF BACKFILL PER PROJECT PLANS.


# CONSTRUCTION SEQUENCE


BOTTOM OF GABION


BOTTOM OF GABION

ALL TOP AND BOTTOM HINGE SPIRALS, AND VERTICAL SIDE SPIRALS ARE FACTORY INSTALLED

# TYPICAL GABION NOT TO SCALE







REV.NO.	DATE	BY	DESCRIPTION
	9/24/98	DR	MINOR REVISIONS
2	4/12/02	DR	UPDATE BORDER
3	12 SEP 07	AMJ	UPDATED BORDER, MINOR REVISIONS
4	15 OCT 15	AMJ	ADDED COLOR TO DETAILS
	27 NOV 19	KBH	ADDED CONTRACT SPECIFIC INFORMATION
6	21 JAN 20	KBH	REMOVE FASCIA BY OTHERS
	06 FEB 20	KBH	UPDATE TYPICAL SECTION
	1 2 3 4 5	1 9/24/98 2 4/12/02 3 12 SEP 07 4 15 OCT 15 5 27 NOV 19 6 21 JAN 20	1 9/24/98 DR 2 4/12/02 DR 3 12 SEP 07 AMJ 4 15 OCT 15 AMJ 5 27 NOV 19 KBH 6 21 JAN 20 KBH

GRAPHIC SCALE

LINE IS 20 UNITS
LONG ON ORIGINAL
DRAWING

0 10 20

NOT TO SCALE

ONE SPIRAL WILL JOIN THE MATS AND THE GABIONS TOGETHER AT ONE TIME.

PROJ.MGR.

ISOMETRIC OF WALL COMPONENTS

ENGINEER
KBH
CADD BY
KBH





1902 Hilfiker Lane
Eureka, CA 95503-5711
TOLL-FREE **800.762.8962**PH **707.443.5093** FAX **707.443.2891**WEBSITE www.hilfiker.com E-MAIL Info@hilfiker.com



DWG DATE	
2/6/20	
DE #01011 DATE	
REVISION DATE	

SCALE

NOTED

CAPACITY OF 2,500 PSF

ARTWELD GABION (EXCLUDE VANEER)
HARRISON SPECIALTY CARE CLINIC
1950 NW MYHRE RD., SILVERDALE, WA 98383
SECTION AND DETAILS

NOT TO SCALE

PROJECT NO. 190801HG SHEET

2 0F 2